MYSORE DIVISION.

The 29th June 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore division, up to 15th July 1897, for restoring the Hondrabalu Tank, Registered No. 74, Chamrajnagar taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th May 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer, and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 (three hundred) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Hondrabalu Tank, Registered No. 74 of Chamrajanagar taluk"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items.	*Abstract of materials.*	*Per.*	*Quantity.*	*Rate.*
Bund—				
Earthwork	.. ..	C. yds.	22,591	
Old stone work	.. ..	„	2,162	
New stone work	.. ..	„	3,005	
Turfing ..	.. ..	S. yd.	11,051	
Jungle clearing	.. ..	L. S.	..	
Grade stone with opposite and bottom stones	.. ..	Each.	45	
Tank number stone	.. ..	„	1	
Gauge stone	.. .. ..	„	1	
Repairs to sluice and constructing waste weirs	.. ..	C. ft.	..	
Excavating foundation	.. .. ..	C. yds.	..	
Brick in surki mortar	.. ..	C. ft.	..	
Surki concrete	.. ..	„	..	
Stone slab coping 6" thick	.. .. ..	R. ft.	..	
New stone sujikat	.. ..	C. yds.	..	
Old stone do	.. ..	„	..	

C. A. MAHADEVA SASTRI, *Executive Engineer.*

HASSAN DIVISION.

SPECIAL REPAIRS OF BANAVASI-KERODI ROAD.

The 3rd July 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan division, up to 20th July 1897, for special repairs of Banavasi-Kerodi road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for special repairs of Banavasi-Kerodi road;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

Items.	*Per.*	*Quantity.*
Metalling.		
Collection of materials—		
Collection of metal, including breaking, stacking and carriage up to ¼ mile.	C. yds.	700
Carriage of metal 1½ miles lead	"	330
Do 2 do	"	370
Collection of gravel, excavating, stacking and carriage up to 1 furlong	"	2,780
Carriage of gravel ½ mile lead	"	1,240
Do 1 do	"	630
Consolidation of materials—		
Picking the road surface	Sq. yds.	26,400
Spreading, watering and consolidating metal	C. yds.	700
Do do gravel	"	180
Do do do	"	2,600
Collecting and spreading sand	"	90
Earthwork	"	640
Ordinary Maintenance.		
Earthwork, widening embankment	C. yds.	2,500
Excavation deepening, side and check drains	"	7,671
Excavating rocky soil	"	172
Removing boulders	"	17
Blasting rock	"	33
Jungle clearing	Lump sum.	
Turfing	Sqr.	456
Cutting laterite stone, hard	C. yds.	53
Removing small stones projecting above road surface	"	50
New mile stones	No.	11
New furlong stones	"	72
Gravel pit stones	"	300
Constructing 17 *new tunnels and repairing* 2 *bridges and lengthening* 11 *tunnels.*		
Rough stone masonry	C. ft.	196
Re-building apron & new stone	C. yd.	7
New stone apron	"	40
Old stone (rough)	"	6
New do	"	111
Excavation	"	180
Burnt brick in mortar	C. ft.	112
Plastering with mortar	Sqr.	1·50
Clearing jungle	Lump sum.	
Removing sandy mound	"	"
New burnt stone slabs set in mortar	S. ft.	206
Rough stone in clay	C. yd.	12
Filling over slabs	"	20
Removing and re-filling old slabs	S. ft.	80

A. S. NAGAVKAR, *Executive Engineer.*